

## FEMALE & MALE RESTROOM

**FLOOR TILES:**  
0.30M X 0.30M UNGLAZED CERAMIC TILES

**WALL TILES:**  
0.30M X 0.60M UNGLAZED CERAMIC TILES

**WATER CLOSET:**  
DUAL FLUSH TWO PIECE WATER CLOSET  
HCG, POZZI OR APPROVED EQUAL

**LAVATORY:**  
LAVATORY WITH PEDESTAL S/S LONGNECK FAUCET  
HCG, POZZI OR APPROVED EQUAL

**FLOOR DRAIN:**  
4" Ø S/S FLOOR DRAIN WITH ODOR ELIMINATOR

**ANGLE VALVES:**  
S/S POZZI, HCG OR APPROVED EQUAL


**FLEXIBLE HOSE:**  
S/S POZZI, HCG OR APPROVED EQUAL

**BIDET:**  
S/S POZZI, HCG OR APPROVED EQUAL

**ACCESORIES:**  
S/S SOAP HOLDER, S/S TISSUE HOLDER


## REST ROOM, SHOWER ROOM & PANTRY'S REFLECTED CEILING PLAN

SCALE 1:100 METERS




## REST ROOM, SHOWER ROOM & PANTRY TILE LAYOUT

SCALE 1:100 METERS




## SECTION 'C'

SCALE 1:100 METERS



## SECTION 'D'

SCALE 1:100 METERS



## SECTION 'E'

SCALE 1:100 METERS

## PANTRY

**COUNTERTOP:**  
SOLID GRANITE SLAB (0.60M X LENGTH)  
WITH SPLASH BACK (0.30M)

**KITCHEN SINK:**  
BRANDED HIGH QUALITY BRUSHED S/S

**KITCHEN FAUCET:**  
BRUSHED S/S GOOSENECK TYPE

**COUNTER CABINET:**  
PRE-FINISH MELAMINE DOORS AND BODY  
KD WOOD SUB FRAMES

**HINGES:**  
S/S HYDRAULIC HINGES

**CATCHES:**  
MAGNETIC

**PULLERS:**  
4" ZEN TYPE S/S PULLER