



C
13
FOUNDATION PLAN
SCALE 1:75 MTS




C3

FOOTING SCHEDULE

MARK	W	L	D	STEEL REINFORCEMENT	CONCRETE STRENGTH, f _c	REMARKS
F - 3	1800 MM	1800 MM	400 MM	20 MMØ @ 200 MM O.C.B.W.	3000 PSI	

COLUMN SCHEDULE

MARK	DIMENSION (A x B)	REBAR SCHEDULE	TIES	F' c PSI
C3	450 MM x 450 MM	8 - 20 MM Ø	10mm Ø LAT. TIES SPACED @ 2 @ 50, 3 @ 100, 4 @ 150, THE REST @ 200mm O.C.	4000 PSI



C3F3 - SECTION

B
13
CONNECTION DETAILS
SCALE 1:75 MTS