

PROJECT : IMPROVEMENT OF THE PROCUREMENT MANAGEMENT DIVISION (PMD) OFFICE
SUBJECT : BILL OF QUANTITIES
LOCATION : PHILRICE-CES, SCIENCE CITY OF MUÑOZ, NUEVA ECIJA

QUANTITY	UNIT	PARTICULARS	UNIT COST	MATERIALS COST	LABOR COST	OCM	PROFIT	TAX	AMOUNT
I. SITEWORKS									
1.00	lot	A. Removal of Existing Wall Patition, Doors, Windows, Laboratory Tables, Cabinets, and Relocation of Door.							
1.00	lot	B. Transfer of Existing Power Outlets / Switches							
II. CARPENTRY WORKS									
1.00	lot	Facial Mirror with Frame with accessories, Sealant, Fiber Glass Signage with Sign Stand Off, Sticker (3M Reflectorized sticker print lettering-green color) for Signage of Procurement Management Division 1/2" Thk. Gypsum Board, 3/4" Marine Plywood, Roll-up Blinds with accessories, 1" x 1" Wood Strip Natural Finish, 1" x 2" Wooden Frame, Assorted CWN, 3.5 mm Hardilite, 3/4" x 2" x 5m x 0.6mm thk Metal Furring, 1/2" x 2" x 5m Carrying Channel, Metal Black Screw 3/4" Consumables							
III. DOORS AND WINDOWS									
1.00	lot	D-4A - 12mm Gray Glass Tinted with Black in Off-white Powder Coated Aluminum Frame Heavy Duty S/S Lock as per approved supplier. GW - 12 mm Gray Glass (fixed) in Off-white Powder Coated Aluminum Frame D-1A - 12mm Gray Glass in Off-white Powder Coated Aluminum Frame Heavy Duty S/S Lock as per approved supplier.							
IV. PAINTING WORKS									
1.00	L.S.	Repainting/Signage (Semi-gloss latex, Tinting color, Flat wall enamel, Quick Dry enamel, Lacquer/Paint Thinner, PaintRoller with Tray , Consumables(rags, old newspaper, sand paper, etc.))							
V. TILE WORKS									
1.00	lot	0.30 x 0.30 Tiles, Cement, White Cement, Tile Adhesive							
VI. OTHERS									
1.00	LS	A. Professional Fees/PMD Signages/PPE's and Etc.							

SUMMARY OF COST

Direct Cost	Material Cost + Labor Cost + Equipment Rental Cost	PhP	
Indirect Cost	OCM	PhP	
	Profit	PhP	
	Tax	PhP	
TOTAL FOR PMD		PhP	

PROJECT : IMPROVEMENT OF THE EXISTING OLD PROPERTY OFFICE TO INTERNAL AUDIT UNIT
SUBJECT : BILL OF QUANTITIES
LOCATION : PHILRICE-CES, SCIENCE CITY OF MUÑOZ, NUEVA ECIJA

QUANTITY	UNIT	PARTICULARS	UNIT COST	MATERIALS COST	LABOR COST	OCM	PROFIT	TAX	AMOUNT
I. SITEWORKS									
1.00	lot	A. Removal of Existing Wall, Doors, and Roofing							
1.00	lot	B. Relocation of Existing Door							
II. MASONRY WORKS									
1.00	lot	4" CHB, Cement, Screened Sand							
III. CEILING WORKS									
1.00	lot	3.5 mm Hardilite, 3/4" x 2" x 5m x 0.6mm thk Metal Furring, 1/2" x 2" x 5m Carrying Channel, Metal Black Screw 3/4", Consumables							
IV. DOORS AND WINDOWS									
21.21	sqm	Analok Frame Window 10mm thk Brown Glass required, Analok Frame Sliding Door with 10mm thk Brown Glass required, Flush Door 9mm thk Ficem Board							
V. PAINTING WORKS									
1.00	L.S.	(Repainting of Interior walls & Ceiling) Semi-gloss latex, Flat wall enamel, Lacquer/Paint Thinner, Paint Roller w/ tray, Consumables(rags, old newspaper, sand paper, etc.)							
VI. TILE WORKS									
1.00	lot	0.60mx0.60m Tiles. Cement, White Cement, Tile Adhesive							
VII. METAL WORKS									
1.00	lot	2" x 4" x 2.0mm Anodized Tubular Bar, 2" x 2" x 1/4" thk Angle Bar, Welding Rod, Consumables (Cutting disk, Bolts, etc)							
VIII. OTHERS									
1.00	lot	Professional Fees,PPE's,and Etc.							

SUMMARY OF COST

Direct Cost		Material Cost + Labor Cost + Equipment Rental Cost		PhP	
Indirect Cost		OCM		PhP	
		Profit		PhP	
		Tax		PhP	
TOTAL FOR IAU				PhP	

PRINTED NAME/SIGNATURE OF AUTHORIZED REPRESENTATIVE

Designation:

Company Name:

Business Address:

PhilGEPS Registration No.:

Telephone Number:

Email Address: