



NOTICE OF AWARD

June 8, 2022

MR. TEODORICO JOSELITO A. TOBIAS

Proprietor
Malachi Enterprise Cons. Corp.
Purok 1, Bakal III, Talavera,
Nueva Ecija

Dear Sir,

We are pleased to inform you that PhilRice awarded you the procurement of the following with reference to your quotation for PR Reference Number 2022-04-1132.

PARTICULARS	DEPT/OFFICE	TOTAL AMOUNT
Procurement of Air Conditioning Units	Procurement Management Division (PMD)	PhP382,200.00

We shall send an approved Purchase Order for the said project at the soonest possible time.

Please acknowledge receipt of this Notice by signing the conforme portion in the space provided below and re-fax or email back to us at frederickcapinpin22@gmail.com within three (3) days from receipt hereof.

For any queries, please coordinate with the Procurement Management Division at telephone number (044) 456-0650.

Thank you very much.

Very truly yours,

Glenda D. Ravelo
GLEND A. RAVELO

Division Head, PMD *GR*

Conforme:

Teodorico Joselito A. Tobias
TEODORICO JOSELITO A. TOBIAS
SIGNATURE OVER PRINTED NAME
Malachi Enterprise Cons. Corp.

June 9, 2022

Date and Time of Receipt



List of Goods/Services for Award to Malachi Enterprise Cons. Corp.

ITEM NO.	QTY	UNIT	ITEM DESCRIPTION	UNIT PRICE	TOTAL PRICE
2	1	unit	<p>Air Conditioner Daikin D-Smart Series Model: FTKQ60TVM / RKQ60TVM Inverter 2.5HP Wall-mounted Circuit Breaker: Schneider *with installation</p> <p>Installation Requirements: Length of Copper tube, Rubber Insulator (all properly covered with vinyl tape):10 feet Circuit breaker:30AT Circuit breaker in NEMA 3R Enclosure gauge #16, single phase Electrical Wire length and size:10 meters Water drain: 20mm.dia. PVC blue pipe</p> <p>Warranty: PCB: 3 years Compressor: 5 years Parts & Services: 1 year</p> <p>*For ASPPD</p>	64,000.00	64,000.00
3	1	unit	<p>Air Conditioner Daikin D-Smart Series Model: FTKQ60TVM / RKQ60TVM Inverter 2.5HP Wall-mounted Circuit Breaker: Schneider *with installation</p> <p>Installation Requirements: Length of Copper tube, Rubber Insulator (all properly covered with vinyl tape):20 feet Circuit breaker:30AT Circuit breaker in NEMA 3R Enclosure gauge #16, single phase Electrical Wire length and size:15 meters Water drain: 20mm.dia. PVC blue pipe</p> <p>Warranty: PCB: 3 years Compressor: 5 years Parts & Services: 1 year</p> <p>*For ODED - Library</p>	70,200.00	70,200.00
4	1	unit	<p>Air Conditioner Daikin D-Smart Series Model: FTKQ35TVM / RKQ35TVM Inverter 1.5HP Wall-mounted Circuit Breaker: Schneider *with installation</p> <p>Installation Requirements: Length of Copper tube, Rubber Insulator (all properly covered with vinyl tape):10 feet Circuit breaker: 30AT Circuit breaker in NEMA 3R Enclosure gauge #16, single phase Electrical Wire length and size:10 meters Water drain: 20mm.dia. PVC blue pipe</p> <p>Warranty: PCB: 3 years Compressor: 5 years Parts & Services: 1 year</p> <p>*For CPD</p>	43,500.00	43,500.00





5	2	unit	<p>Air Conditioner Daikin D-Smart Series Model: FTKQ60TVM / RKQ60TVM Inverter 2.5HP Wall-mounted Circuit Breaker: Schneider</p> <p>*with installation</p> <p>Installation Requirements: Length of Copper tube, Rubber Insulator (all properly covered with vinyl tape):10 feet Circuit breaker: 30AT Circuit breaker in NEMA 3R Enclosure gauge #16, single phase Electrical Wire length and size:10 meters Water drain: 20mm.dia. PVC blue pipe</p> <p>Warranty: PCB: 3 years Compressor: 5 years Parts & Services: 1 year</p> <p>*For PBBD</p>	64,000.00	128,000.00
6	1	unit	<p>Air Conditioner Daikin D-Smart Series Model: FTKQ60TVM / RKQ60TVM Inverter 2.5HP Wall-mounted Circuit Breaker: Schneider</p> <p>*with installation</p> <p>Installation Requirements: Length of Copper tube, Rubber Insulator (all properly covered with vinyl tape):50 feet Circuit breaker:30AT Circuit breaker in NEMA 3R Enclosure gauge #16, single phase Electrical Wire length and size:20 meters Water drain: 20mm.dia. PVC blue pipe</p> <p>Warranty: PCB: 3 years Compressor: 5 years Parts & Services: 1 year</p> <p>*For FMD</p>	76,500.00	76,500.00
				TOTAL	382,200.00

Prepared by:

FREDERICK P. CAPINPIN
 Admin Assistant III

